

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-14816-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 22-18S-11W  
4950 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: OBERLE Well #: 4  
County: BARTON Total Vertical Depth: 3338 feet

Operator License No.: 34935  
Op Name: DEXXON, INC.  
Address: P O BOX 348  
KIEFER, OK 74041

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3314		200 SX
SURF	10.75	610		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/02/2017 8:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: BRIAN OBERLE Company: DEXXON, INC. Phone: (620) 793-2299

Proposed  
Plugging  
Method:

Ordered 200 sx common cement w/3% cc, 200 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/02/2017 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400' and 590'. Ran tubing to 3250' and pumped 13 sx gel followed by 50 sx common cement w/3% cc and 200 # hulls. Pulled tubing to 1400' and pumped 80 sx common cement w/3% cc and 200 # hulls. Pulled tubing to 600'. Circulated cement to surface on casing with 135 sx cement. Pulled tubing. Tied to casing. Circulated cement to surface on surface pipe with 70 sx cement.

GPS: 38.47753 -098.53478

Perfs:

Top	Bot	Thru	Comments
3317	3338		
3026	3314		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Received Signed Bruce Rodie  
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

NOV 20 2017

CONSERVATION DIVISION  
WICHITA, KS

NOV 06 2017

Form CP-2/3

INVOICED  
DEC 13 2017