

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-21155-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 32-33S-12E  
1519 feet from S Section Line, 3459 feet from E Section Line  
Lease Name: ALFORD A L Well #: 36  
County: CHAUTAUQUA Total Vertical Depth: 1115 feet

Operator License No.: 5970  
Op Name: ELMORE, JOHN A. OR PATRICIA R.  
Address: 776 HWY 99  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1115		20 SX
SURF	7	40		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/29/2017 10:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: JOHN ELMORE Company: \_\_\_\_\_ Phone: (620) 249-2519

Proposed Plugging Method: Run 1" to 1080' gel hole spot 5 sacks cement pull 1" out perforate casing at 600' and at 350'. Run 1" to 600' spot 5 sacks cement pull up to 350' cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/29/2017 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1050' gelled hole and spotted 5 sack plug. Pulled 1" and shot 4.5" casing off at 500'. Pulled casing. Ran 1" back into 500' and spotted 10 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 88 sacks of cement were used to plug this well.

Perfs:

RECEIVED  
KCC DIST # 3  
NOV 21 2017  
CHANUTE, KS

DS

INVOICED  
DEC 13 2017

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)