

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24625-00-00
Spot: SWSWNESE Sec/Twnshp/Rge: 3-17S-25W
1572 feet from S Section Line, 1200 feet from E Section Line
Lease Name: MOLLENKAMP Well #: 1
County: NESS Total Vertical Depth: 4535 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1865		WITH 275 SX CMT
PROD	5.5	4534		WITH 150 SX CMT
SURF	8.625	210		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/09/2017 9:00 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Revd. from: VAL DREHER Company: FARMER, JOHN O., INC. Phone: (785) 483-8356

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 200# HULLS. SPACER TO 1870'. CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/09/2017 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 35 SX CMT WITH 200# HULLS AT 4400'. PUMP 190 SX CMT FROM 1870' TO 0'. TOP OFF WITH 20 SX CMT. ATTEMPT TO PUMP CMT DOWN THE ANNULUS. COULD NOT. ANNULUS FULL.

Perfs:

Top	Bot	Thru	Comments
4477	4482		MISSISSIPPI

INVOICED
DEC 13 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

District: 01

Signed

[Signature]
(TECHNICIAN)

5A

RECEIVED
OCT 17 2017
KCC DODGE CITY