

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-20626-00-00
Spot: SESWNENW Sec/Twnshp/Rge: 17-12S-17W
4104 feet from S Section Line, 3500 feet from E Section Line
Lease Name: SCHMEIDLER A Well #: 8
County: ELLIS Total Vertical Depth: 3687 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: 114 NORTH MAIN P.O. BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3685		175 SX
SURF	8.625	615		450 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/30/2017 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: DAVE HEIM Company: GRADY BOLDING CORPORATION Phone: (785) 623-2084

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement and 500 # hulls.
Alt l completed.
Perforations: 3685' - 3687' Arb OH.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/30/2017 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated at 580'. Professional Pulling Services ran in hole with tubing to 3600'. Quality rigged to tubing and pumped 13 sx gel followed by 150 sx cement w/150 # hulls mixed in. Pulled tubing to 1832' and pumped 180 sx cement w/200 # hulls mixed in to circulate cement up 5 1/2" casing. Pulled tubing. Rigged to 5 1/2" casing with a swage and pumped 100 sx cement to circulate cement up 8 5/8" casing. Shut in. Hole standing full.

GPS: 39.01312 -099.23547

Perfs:

Top	Bot	Thru	Comments
3685	3687		

INVOICED
DEC 14 2017

INVOICED
DEC 14 2017

Remarks: QUALITY OIL WELL CEMENTING TICKET # 332

Plugged through: TBG

District: 04

Signed _____

[Signature]
(TECHNICIAN)

CM

NOV 06 2017

Received
KANSAS CORPORATION COMMISSION

NOV 20 2017

CONSERVATION DIVISION
WICHITA, KS