

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-05115-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 8-12S-17W
293 feet from S Section Line, 4379 feet from E Section Line
Lease Name: SCHMEIDLER B Well #: 3
County: ELLIS Total Vertical Depth: 3699 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: 114 NORTH MAIN P.O. BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3673		250 sx
SURF	8.625	175		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/24/2017 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: DAVE HEIN Company: GRADY BOLDING CORPORATION Phone: (785) 623-2084

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 600 # hulls and 12 sx gel.
DV Tool at 1430' w/400 sx portland cement.
Perforations: 3432' - 3437', 3451' - 3454', 3490' - 3492' and 3497' - 3504'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2017 5:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Professional Pulling Services ran in hole with tubing to 3500' and pumped 12 sx gel followed by 50 sx cement w/300 # hulls mixed in. Pulled tubing to 1850' and pumped 190 sx cement w/300 # hulls mixed in to circulate cement up 5 1/2" casing. Rig broke down. Dropped 35 joints of tubing in hole. Topped off 5 1/2" casing with 35 sx cement. Cement came out of hole in 8 5/8" surface casing near surface.

GPS: 39.01709 -099.23837

Perfs:

Top	Bot	Thru	Comments
3497	3504		
3490	3492		
3451	3454		
3432	3437		

INVOICED

DEC 1 2017

Remarks: QUALITY CEMENTING CO TICKET # 328

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

OCT 26 2017

Received
KANSAS CORPORATION COMMISSION

NOV 20 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3