

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21051-00-00
Spot: NWNESENW Sec/Twnshp/Rge: 8-30S-18W
3639 feet from S Section Line, 2981 feet from E Section Line
Lease Name: PARKIN Well #: 1-D
County: KIOWA Total Vertical Depth: 5170 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4975		WITH 2 SX CMT
PROD	4.5	5169	0	WITH 300 SX CMT
SURF	8.625	477		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/04/2017 10:30 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: TRACY HOLLIS Company: HERMAN L LOEB Phone: (719) 340-8985

Proposed Plugging Method: CIBP @ 4975' WITH 2 SX CMT. LOAD HOLE & TEST CASING. IF CASING TESTS GOOD, PERFORATE AT 1200' & PUMP 10 SX GEL & 50 SX CMT WITH 100# HULLS IN LAST 25 SX. PERFORATE AT 500' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/04/2017 1:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP AT 4975' WITH 2 SX CMT. LOADED THE HOLE & PRESSURED THE CASING TO 300#. PERFORATED AT 1200' & 500'. RAN TBG TO 1208' & PUMPED 10 SX GEL, 25 SX CMT THEN 25 SX CMT WITH 100# HULLS. PULLED TBG TO 508'. CIRCULATED CMT INSIDE OF 4 1/2" WITH 100 SX CMT THEN OUTSIDE OF 4 1/2" WITH 125 SX CMT. PULLED TBG & TOPPED OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Tru	Comments
5024	5034	CSG	

INVOICED

OCT 14 2017

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
OCT - 9 2017
KCC DODGE CITY