

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-21202-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 3-35S-12W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: LOHMANN Well #: 7-A
County: BARBER Total Vertical Depth: 4875 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4790		WITH 2 SX CMT
PROD	4.5	4871	40	WITH 125 SX CMT
SURF	8.625	327		WITH 275 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2017 9:00 AM
Plug Co. License No.: 35383 Plug Co. Name: STERLING OILFIELD SERVICES, INC.
Proposal Rcvd. from: ALAN VRATIL Company: HERMAN L LOEB LLC Phone: (620) 886-2419

Proposed Plugging Method: CIBP @ 4790' WITH 2 SX CMT ON TOP. CUT & PULL 4 1/2" CASING. PLUG AT 620' WITH 10 SX GEL & 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAJER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2017 12:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 4790' WITH 2 SX CMT ON TOP. CUT CASING & TRIED TO PULL. CASING PARTED ONE JOINT DOWN FROM SURFACE. WAS ABLE TO GET INTO 4 1/2" CASING WITH GUN & PERFORATE AT 620'. PUMP 150 SX CMT TO CIRCULATE TO SURFACE. CONFIRM BACKSIDE FULL OF CMT. HOLE REMAINING FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4838	4846		

INVOICED
DEC 14 2017

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC SERVICES.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
NOV - 9 2017
KCC DODGE CITY [Signature]

JA