

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-21547-00-00
Spot: SESWNE Sec/Twnshp/Rge: 35-26S-13W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: PIERPOINT Well #: 4
County: PRATT Total Vertical Depth: 4390 feet

Operator License No.: 4997
Op Name: HOENER, ROSS
Address: 70424 NE 10TH AVE
IUKA, KS 67066

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| PROD | 5.5 | 4389 | 746 | WITH 200 SX CMT |
| SURF | 8.625 | 472 | | WITH 125 SX CMT |

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/25/2017 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DEREK BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4180' WITH 2 SX CMT. PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 60' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 10/25/2017 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED BACK TO 4150' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 480' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 35 SX CMT. TOP OFF 8 5/8" SURFACE PIPE WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4265 | 4271 | CSG | |
| 4217 | 4248 | CSG | |

INVOICED
GL: 1-4 2017

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed *Ken Seefeldt*
SA (TECHNICIAN)

RECEIVED
NOV - 3 2017
KCC DODGE CITY
11-3-17