

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21593-00-00
Spot: SWNENWNE Sec/Twnshp/Rge: 20-26S-8E
4880 feet from S Section Line, 1918 feet from E Section Line
Lease Name: DRUMM Well #: 4
County: BUTLER Total Vertical Depth: 2800 feet

Operator License No.: 35164
Op Name: JIM SNYDER, INC.
Address: PO BOX 109
HAMILTON, KS 66853

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD | 4.5 | 2798 | | 100 SX |
| SURF | 7 | 261 | | 260 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/25/2017 8:00 AM
Plug Co. License No.: 35164 Plug Co. Name: JIM SNYDER, INC.
Proposal Rcvd. from: JOEL SNYDER Company: _____ Phone: (620) 344-6042

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 10/26/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

DUMP BAILED 2 SXS CEMENT ON TOP OF PACKER @ 1257'. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 311'-312' (2 HOLES). 10/26/2017 RIH W/1" TUBING @ 320', ELITE CEMENTING ESTABLISHED CIRCULATION MIXED & PUMPED 90 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED INSIDE AND OUTSIDE CASING. CEMENT TICKET # 3591.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2700 | 2732 | CSG | |

INVOICED
OCT 14 2017

Remarks: COMPLIANCE/ TA COMPLIANCE AGREEMENT

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

1/4