

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-20773-00-02
Spot: SWNENW Sec/Twnshp/Rge: 29-26S-8E
4275 feet from S Section Line, 3744 feet from E Section Line
Lease Name: DRUMM Well #: 12
County: BUTLER Total Vertical Depth: 2770 feet

Operator License No.: 35164
Op Name: JIM SNYDER, INC.
Address: PO BOX 109
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2769		100 SX
SURF	8.625	198		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/25/2017 8:00 AM
Plug Co. License No.: 35164 Plug Co. Name: JIM SNYDER, INC.
Proposal Revd. from: JOEL SNYDER Company: _____ Phone: (620) 344-6042

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 10/26/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SET CIBP @ 2570'. DUMP BAILED 2 SX CEMENT ON TOP OF PLUG. PERFORATED SQUEEZE HOLES 250'-251'. (2 HOLES) 10/26/2017 RIH W 1" TUBING ON INSIDE OF 4 1/2" CASING @ 260'. ELITE ESTABLISHED CIRCULATION, MIXED & PUMPED 30 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN 1" TUBING. RIH W/1" TUBING ON BACKSIDE OF 4 1/2" CASING @ 260', ELITE ESTABLISHED CIRCULATION, MIXED & PUMPED 70 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING, TOPPED WELL BACK TO SURFACE W/ 5 SXS. CEMENT TICKET #3592.

Perfs:

Top	Bot	Thru	Comments
2699	2732		CSG
2620	2637		CSG

INVOICED
DEC 14 2017

Remarks: COMPLIANCE / TA COMPLIANCE AGREEMENT

Plugged through: TBG

District: 02

Signed

Jeff Klock DISTRICT SUPERVISOR
(TECHNICIAN)

JK