

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-057-20988-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 22-29S-22W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: SELLARD Well #: 1-22
County: FORD Total Vertical Depth: 5430 feet

Operator License No.: 31822 String Size Depth (ft) Pulled (ft) Comments
Op Name: JOLEN OPERATING COMPANY SURF 8.625 521 WITH 320 SX CMT
Address: 100 N BROADWAY AVE STE 2460
OKLAHOMA CITY, OK 73102

Well Type: DH UIC Docket No: Date/Time to Plug: 10/23/2017 9:30 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: MIKE GODFREY Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 570' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 10/23/2017 11:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:


1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 570' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: DP

District: 01

Signed



(TECHNICIAN)

RECEIVED
OCT 24 2017
KCC DODGE CITY

