

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-24301-00-00  
Spot: S2S2N2NE Sec/Twnshp/Rge: 31-31S-12W  
1100 feet from N Section Line, 1320 feet from E Section Line  
Lease Name: TOM Well #: 1  
County: BARBER Total Vertical Depth: 4528 feet

Operator License No.: 35268  
Op Name: JRG PETROLEUM LLC  
Address: PO BOX 149  
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4150		WITH 2 SX CMT
CIBP		4410		
CIBP		4485		
PROD	4.5	4524	2980	WITH 250 SX CMT
SURF	8.625	262		WITH 180 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/31/2017 11:30 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: JR GRIFFIN Company: JRG PETROLEUM Phone: (620) 825-6260

Proposed Plugging Method: SRT CIBP @ 4150' WITH 2 SX CMT. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN SCOFIELD WitnessType: NONE  
Date/Time Plugging Completed: 10/31/2017 12:15 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 4150' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 601' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 66' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4447	4455		
4204	4224		

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

DEC 14 2017

Plugged through: TBG

District: 01

RECEIVED  
NOV - 3 2017  
KCC DODGE CITY

Signed Ken Scofield  
(TECHNICIAN)