

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-22481-00-00
Spot: SENW Sec/Twnshp/Rge: 20-18S-11W
3300 feet from S Section Line, 3300 feet from E Section Line
Lease Name: KRIER Well #: 1
County: BARTON Total Vertical Depth: 3473 feet

Operator License No.: 9951
Op Name: KRIER, KIRBY OIL, INC.
Address: 1043 NE 80TH RD
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3473		100 SX
SURF	8.625	252		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/23/2017 8:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: KIRBY KRIER Company: KRIER, KIRBY OIL, INC. Phone: (620) 562-7637

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 13 sx gel.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/23/2017 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 670' and 250'. Ran tubing to 3200' and pumped 13 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1350' and pumped 70 sx cement w/200 # hulls. Pulled tubing to 670'. Circulated cement to surface with 90 sx cement. Pulled tubing. Topped off with 15 sx cement. Surface pipe squeezed had cement in braden head.

GPS: 38.47293 -098.56470

Perfs:

Top	Bot	Thru	Comments
3306	3310		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

INVOICED
DEC 14 2017

District: 04

Signed Bruce Rodie
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

NOV 20 2017

CONSERVATION DIVISION
WICHITA, KS

CM

NOV 27 2017

Form CP-2/3