

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-24936-00-00  
Spot: NENWNWSE Sec/Twnshp/Rge: 1-20S-14W  
2500 feet from S Section Line, 2150 feet from E Section Line  
Lease Name: BUSH Well #: 4  
County: BARTON Total Vertical Depth: 3610 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3613	2200	175 SX
SURF	8.625	793		335 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/30/2017 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KASSELMAN Company: L. D. DRILLING, INC. DBA Phone: (620) 793-3051

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/30/2017 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off with 5 sx cement. Cut casing at 2200'. Pulled casing to 1400' and pumped 125 sx cement w/300 # hulls. Pulled casing to 800' and pumped 50 sx cement w/100 # hulls. Pulled casing to 500' and pumped 50 sx cement w/100 # hulls. Pulled casing to 200'. Circulated with 75 sx cement. Pulled casing and hole stayed full.

GPS: 38.33947 -098.81867

Perfs:

Top	Bot	Thru	Comments
3277	3282		

Remarks: BASIC CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie  
Received  
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

NOV 06 2017

NOV 20 2017

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

INVOICED

10/31/2017