

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-22404-00-00
Spot: SENENW Sec/Twnshp/Rge: 35-19S-12W
990 feet from N Section Line, 2310 feet from W Section Line
Lease Name: HAMMER Well #: 1
County: BARTON Total Vertical Depth: 3363 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3360		150 SX
SURF	8.625	209		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2017 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L. D. DRILLING, INC. DBA Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 #hulls.
Started to sand off bottom to pull casing. Sand bridged off at 200'. Worked through bridge down to 1400'. Operator thinks casing parted and tubing stacked out on something hard. Holes in casing from 1400' to surface. District supervisor approved plugging from this depth.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/20/2017 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 1390' and pumped 50 sx cement. Pulled tubing to 650'. Circulated cement to surface with 55 sx cement. Pulled tubing. Tied to casing and circulated cement to surface with 130 sx cement. Cement came up around and inside surface pipe.

GPS: 38.35920 -098.61929

Perfs:

Top	Bot	Thru	Comments
3332	3340		

INVOICED

10/20/17

Remarks: BASIC CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

NOV 20 2017

CONSERVATION DIVISION

OCT 27 2017