

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24915-00-00
Spot: SESWNENW Sec/Twnshp/Rge: 12-20S-14W
1150 feet from N Section Line, 1910 feet from W Section Line
Lease Name: BUSH Well #: 3
County: BARTON Total Vertical Depth: 3620 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3623		150 SX
SURF	8.625	826		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/24/2017 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L. D. DRILLING, INC. DBA Phone: (620) 793-3051

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2017 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off with 5 sx cement. Cut casing at 1690'. Pulled casing to 1400' and pumped 125 sx cement w/300 # hulls. Pulled casing to 800' and pumped 50 sx cement w/200 # hulls. Pulled casing to 500' and pumped 50 sx cement. Pulled casing to 200'. Circulated with 106 sx cement.

GPS: 38.32945 -098.82272

Perfs:

Top	Bot	Thru	Comments
3353	3359		

INVOICED

DEC 14 2017

Remarks: BASIC CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
Received _____
KANSAS CORPORATION COMMISSION (TECHNICIAN) CM

NOV 20 2017

CONSERVATION DIVISION
WICHITA, KS

OCT 27 2017