

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23999-00-00
Spot: E2NWNENE Sec/Twnshp/Rge: 1-23S-12W
330 feet from N Section Line, 735 feet from E Section Line
Lease Name: FIGGER Well #: 1
County: STAFFORD Total Vertical Depth: 3547 feet

Operator License No.: 32432
Op Name: LA VETA OIL & GAS, LLC
Address: 305 N BUFFALO
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	269		WITH 250 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/11/2017 6:15 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: WES PFAFF Company: SOUTHWIND DRILLING, INC. Phone: (620) 564-3800

Proposed Plugging Method: 1ST PLUG AT 3534' WITH 50 SX CMT. 2ND PLUG AT 810' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 10/11/2017 8:15 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:


1ST PLUG AT 3534' WITH 50 SX CMT. 2ND PLUG AT 806' WITH 50 SX CMT. 3RD PLUG AT 310' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.


Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: DP

District: 01

Signed  (TECHNICIAN)

RECEIVED
OCT 11 2017
KCC DODGE CITY 

INVOICED
OCT 11 2017

KMS