

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2-070806

11-6

API Number: 15-159-21897-0000

SW NW NW SECTION 12 TWP 21 RANGE 07W

OPERATOR LICENSE #31925
OPERATOR QUALITY WELL SERVICE
NAME & 249 BETH DRIVE
ADDRESS STERLING, KS 67579-9048

4290 FEET FROM S SECTION LINE
4950 FEET FROM E SECTION LINE

LEASE NAME MAXI #7
COUNTY RICE
WELL TOTAL DEPTH 3530' 11-6-73
PIPE 5 1/2" @ 3526'
SURFACE CASING 8 5/8" @ 218'

ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐ SWD ☐ D&A ☐

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: QUALITY WELL SERVICE

ADDRESS: STERLING, KS 67579 LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 6 MONTH: 11 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: JOE MASE

COMPANY NAME: QUALITY WELL SERVICE PHONE: (316) 727-3410

WERE: SAND TO 3400' AND 5 SACKS OF COMMON. 35 SACKS @ 1050'. 35 SACKS @ 650'. 268' TO 0.

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ☐ PART ☒ NONE ☐

COMPLETED: HOUR: 2:30 DAY: 6 MONTH: 11 YEAR: 1998

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3400' AND 5 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 2970'. PULLED TO 1050'. PUMPED 35 SACKS. PULLED TO 650'. PUMPED 35 SACKS. PULLED TO 268'. CIRCULATED CEMENT TO SURFACE.

REMARKS: ALLIED #7711, 60/40 POZ, 4% GEL

I DID OBSERVE THIS PLUGGING

JACK LUTHI

FORM CP-2/3
REV. 3/90

11-13-98

60345-