

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2-070803

API Number: 15-159-21,910-0000

SW SW NW SECTION 12 TWP 21 RANGE 07W

OPERATOR LICENSE 31925
OPERATOR QUALITY WELL SERVICE
NAME & ADDRESS 249 BETH DRIVE
STERLING, KS 67579

3100 FEET FROM S SECTION LINE
4950 FEET FROM E SECTION LINE
LEASE NAME _____ MAXI #8
COUNTY RICE
WELL TOTAL DEPTH 3530' 114.73
PIPE 5 1/2" @ 3509'
SURFACE CASING 8 5/8" @ 210'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: QUALITY WELL SERVICE

ADDRESS: STERLING, KS 67579 LICENSE: 31925

COMPANY TO PLUG AT: _____ HOUR: 2:00 DAY: 21 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: RICHARD MCINTYRE

COMPANY NAME: QUALITY WELLS SERVICE PHONE: (316)727-3410

WERE: SAND TO 3390' AND 5 SACKS
35 SACKS @ 1050'
35 SACKS @ 600'
260' TO 0'

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 03 1998

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI CONSERVATION DIVISION
WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART _____ NONE _____

COMPLETED: HOUR: 5:00 DAY: 21 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3390' AND 5 SACKS. SHOT 5 1/2" CASING OFF AT 2400'. PULLED TO 1050'. PUMPED 35 SACKS. PULLED TO 600'. PUMPED 35 SACKS. PULLED TO 260' CIRCULATE CEMENT TO SURFACE.

REMARKS: ALLIED CEMENTING #5223, 60/40 POZ, 4% GEL.

I DID OBSERVE THIS PLUGGING.

Jack Luthi
JACK LUTHI

FORM CP-2/3
REV. 3/90

11-4-98
DW 60249