

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2-090553

API Number: 15-159-21,733-0000

C N/2 N/2 NW SECTION 12 TWP 21 RANGE 07W

OPERATOR LICENSE #31925 4950 FEET FROM S SECTION LINE
OPERATOR QUALITY WELL SERVICE 3960 FEET FROM E SECTION LINE
NAME & 249 BETH DRIVE
ADDRESS STERLING, KS 67579-9048

LEASE NAME _____
COUNTY RICE
WELL TOTAL DEPTH 3557' 115.61
PIPE 5 1/2" @ 3557'
SURFACE CASING 8 5/8" @ 215'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: QUALITY WELL SERVICE

ADDRESS: 249 BETH DRIVE, STERLING, KS 67579-9048 LICENSE: 31925

COMPANY TO PLUG AT: _____ HOUR: 8:00 DAY: 26 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: RICHARD

COMPANY NAME: QUALITY WELL SERVICE PHONE: (316) 727-3410

WERE: SAND TO 3450'. CAP WITH 5 SACKS OF CEMENT. SHOOT FOR RECOVERY.

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 03 1998

PLUGGING PROPOSAL RECEIVED BY: RALPH TITTEL CONSERVATION DIVISION
WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL _____ PART NONE _____

COMPLETED: HOUR: 14:00 DAY: 26 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT: SANDED TO 3450'. CAPPED WITH 5 SACKS OF CEMENT. RECOVERED 2642' OF 5 1/2"
THROUGH 5 1/2" SPOTTED 35 SACKS @ 1050', 35 SACKS @ 600' AND CIRCULATED FROM 265' TO SURFACE.

REMARKS: UNITED 150 SACKS, 60/40 POZ, 4% GEL.

I DID OBSERVE THIS PLUGGING.

Ralph Tittel
RALPH TITTEL

FORM CP-2/3
REV. 3/90

11-4-98
60249