

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

10-19

2-070801

API Number: 15-159-21,711-0000

NW NW SW SECTION 12 TWP 21 RANGE 07W

OPERATOR LICENSE #31925  
OPERATOR QUALITY WELL SERVICE INC.  
NAME & ADDRESS 249 BETH DRIVE  
STERLING, KS 67579-9048

2310 FEET FROM S SECTION LINE  
4950 FEET FROM E SECTION LINE

LEASE NAME PALLISTER #1  
COUNTY RICE  
WELL TOTAL DEPTH 3498' 113.69  
PIPE 5 1/2" @ 3496'  
SURFACE CASING 8 5/8" @ 203'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: QUALITY WELL SERVICE

ADDRESS: STERLING, KS 67579-9048 LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 2:00 DAY: 19 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: RICHARD MCINTYRE

COMPANY NAME: QUALITY WELL SERVICE PHONE: (316) 727-5410

WERE: SAND TO 3350' AND 5 SACKS  
35 SACKS - 1000'  
35 SACKS - 650'  
250' TO 0

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 22 1998

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL  PART  NONE   
CONSERVATION DIVISION WICHITA, KS

COMPLETED: HOUR: 5:00 DAY: 19 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3350' AND 5 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 2400'. PULLED TO 1000'. PUMPED 35 SACKS. PULLED TO 650'. PUMPED 35 SACKS. PULLED TO 250'. CIRCULATE CEMENT TO SURFACE.

REMARKS: UNITED #5221, 60/40 POZ, 4% GEL.

I DID OBSERVE THIS PLUGGING.

*Jack Luthi*  
JACK LUTHI

FORM CP-2/3  
REV. 3/90

10-23-98

60186 10-19

JAN 29 1999