

3-10-88

1 120079

API NUMBER 15-165-21,010-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE NE, SEC. 1, T 16 S, R 19 W/EX

3630 feet from S section line

990 feet from E section line

Lease Name Werth Well # 1

County Rush 118.30

Well Total Depth 3640 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1184

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067

Operator: DaMar Resources

Name &

Address P.O. Box 70

Hays, KS 67601

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Wilson Casing Pulling License Number 3158

Address P.O. Box 991, Woodward, OK

Company to plug at: Hour: 2 p.m. Day: 10 Month: 3 Year: 19 88

Plugging proposal received from

(company name) Wilson Casing Pulling (phone) 405-256-6023

were: 5 1/2" at 3630' PBSD 3575' Perfs at 3180-3617' (7 sets) Elevation 1989' GL TOC 2220'

1st plug sand back to 50' above perfs and dump 5 sx cement on top of sand through bailer,

2nd plug pump 5 sx hulls and 200 sx ATL cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 p.m. Day: 10 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 50' above perfs. with 5 sx cement on top,

2nd plug pumped into 8 5/8" surface casing with 500 lbs. hulls and 200 sx ATL cement.

STATE CORPORATION COMMISSION

Pumping pressure 0-850 psi and shut in 300 psi.

MAR 16 1988
3-16-1988

Operator stated that 8 5/8" was full of water after pulling 5 1/2".

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used ATL cement by Allied. Recovered 2015' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (and observe this plugging.)

Signed Duane Rankin (TECHNICIAN)

DATE 3-16-88

INV. NO. 20126

3-10 APR 14 1988