

TO: 1070077 7-28 API NUMBER 15-097-21,425 - 0000

STATE CORPORATION COMMISSION SE NE SE, SEC. 18, T 28 S, R 19 W
CONSERVATION DIVISION - PLUGGING SECTION 1620 FEET FROM SOUTH SECTION LINE
WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE
WICHITA, KANSAS 67202 LEASE NAME Olsen Test Well WELL # 1
TECHNICIAN'S PLUGGING REPORT COUNTY Kiowa 188.50
OPERATOR LICENSE # 9362 WELL TOTAL DEPTH 5800' FEET
OPERATOR: Williams Natural Gas Co. PRODUCTION CSG: SIZE FEET
NAME AND P.O. Box 3288 MD 32-3 SURFACE CASING: SIZE 13 3/8" FEET 630'
ADDRESS Tulsa, Oklahoma 74101
ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED
PLUGGING CONTRACTOR Pratt Well Service LICENSE NUMBER 5893
ADDRESS P.O. Box 847, Pratt, Kansas 67124-0847
COMPANY TO PLUG AT: HOUR: 3:00p.m. DAY 28 MONTH: 7 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM Thomas Cook
(COMPANY NAME) Williams Natural Gas Co. (PHONE) (918) 588-3330

WERE: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 5330' with 50 sx cement, 2nd plug at 1895' with 50 sx cement
3rd plug at 630' with 65 sx cement,
4th plug at 40' with 20 sx cement, 5th plug to circulate rathole with 15 sx cement
6th plug to circulate mousehole with 10 sx PLUGGING PROPOSAL RECEIVED BY Steve Durrant

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE
OPERATIONS COMPLETED: HOUR: 6:45 p.m. Day: 28 MONTH: 7 YEAR: 1998

ACTUAL PLUGGING REPORT 1st plug at 5330' with 50 sx
2nd plug at 1895' with 30 sx, 3rd plug at 1860' with 20 sx
4th plug at 620' with 65 sx, 5th plug at 40' with 20 sx
6th plug to circulate rathole with 15 sx cement
7th plug to circulate mousehole with 10 sx cement

Note: The 1st, 2nd, 6th and 7th plugs were completed on 9/10/97; The 3rd, 4th & 5th
plugs were completed on 7/28/98. The 3rd, 4th and 5th plugs were witnessed.

REMARKS: Used 60/40 Pozmix 4% Gel 3% CC, by Allied
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.
SIGNED (TECHNICIAN) FORM CP-2/3

RECEIVED
WILLIAMS NATURAL GAS CO.
8-5-98

INVOICED
AUG 10 1998
DATE
INV. NO. 51140
7-28