

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-057-20104-00-01  
Spot: NWSESENE Sec/Twnshp/Rge: 25-25S-21W  
2096 feet from N Section Line, 657 feet from E Section Line  
Lease Name: HERRMANN C Well #: 1  
County: FORD Total Vertical Depth: 4800 feet

Operator License No.: 32457  
Op Name: ABERCROMBIE ENERGY, LLC  
Address: 10209 W. CENTRAL, STE 2  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1129		CMT TO SURFACE
PROD	4.5	4798	0	WITH 185 SX CMT
SURF	8.625	370		WITH 300 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2017 1:00 PM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: TIM JULIAN Company: ABERCROMBIE ENERGY Phone: (620) 793-8185

Proposed Plugging Method: PLUG AT 4600' WITH 150# HULLS & 35 SX CMT. PLUG AT 1400' TO SURFACE. TOP OFF. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/01/2017 3:50 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

RAN TBG TO 4591' & PUMPED 35 SX CMT WITH 150# HULLS. PULLED TBG TO 1401' & PUMPED 150 SX CMT. NO CIRCULATION. PULLED TBG TO 1082' & CIRCULATED CMT TO SURFACE WITH 25 SX CMT. PULLED TBG & TOPPED OFF WITH 15 SX CMT. HOLE STAYED FULL. BACKSIDE WAS FULL.

Perfs:

Top	Bot	Thru	Comments
4697	4700		

NOV 1 3 2017  
INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
NOV - 3 2017  
KCC DODGE CITY

[Signature]

[Signature]