

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-057-20531-00-00
Spot: NESWSESE Sec/Twnshp/Rge: 24-25S-21W
575 feet from S Section Line, 753 feet from E Section Line
Lease Name: FIELD Well #: 1
County: FORD Total Vertical Depth: 4840 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| DVT | 4.5 | 1093 | | WITH 400 SX CMT |
| PROD | 4.5 | 4838 | 0 | WITH 185 SX CMT |
| SURF | 8.625 | 292 | | WITH 200 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2017 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: TIM JULIAN Company: ABERCROMBIE ENERGY Phone: (620) 793-8185

Proposed Plugging Method: PLUG AT 4700' WITH 35 SX CMT & 150# HULLS. PLUG AT 1400' & CIRCULATE CMT TO SURFACE. TOP OFF. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2017 1:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

1ST PLUG AT 4670' WITH 35 SX CMT & 150# HULLS. 2ND PLUG AT 1400'.
CIRCULATED CMT TO SURFACE WITH 100 SX CMT. PULLED TBG & TOPPED OFF
WITH 20 SX CMT. BACKSIDE WAS FULL.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4753 | 4756 | | |
| 4702 | 4705 | | |

INVOICED
DEC 13 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 01

Signed

Larry Harris
(TECHNICIAN)

RECEIVED
NOV - 3 2017
KCC DODGE CITY