

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-21384-00-00
Spot: E2SWNW Sec/Twnshp/Rge: 30-25S-20W
3341 feet from S Section Line, 4402 feet from E Section Line
Lease Name: HERRMAN B Well #: 1
County: EDWARDS Total Vertical Depth: 4820 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4735		
PROD	5.5	4823	0	WITH 210 SX CMT
SURF	8.625	355		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/03/2017 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: TIM JULIAN Company: ABERCROMBIE ENERGY Phone: (620) 793-8185

Proposed Plugging Method: PLUG AT 4650' WITH 50 SX CMT & 200# HULLS. PERFORATE AT 1400' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/06/2017 12:50 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

11/3/17: PERFORATED AT 1400'. RAN TBG TO 4638' & PUMPED 50 SX CMT WITH 200# HULLS. PULLED TBG TO 1401' & PUMPED 190 SX CMT. CASING RETURN LINE WENT FROM A STRONG BLOW TO A VACUUM THEN TO A SLIGHT BLOW. PULLED TBG TO 1082' & PUMPED THE LAST 25 SX CMT. RETURN LINE HAD A BLOW BUT RAN OUT OF CMT BEFORE CIRCULATING. PULLED TBG. WILL TAG TOC. 11/6/17: TAGGED CMT AT 1210'. PULLED TBG OUT OF HOLE. PERFORATED AT 500'. RAN TBG TO 510' & CIRCULATE CMT WITH 85 SX CMT. PULLED TBG & TOPPED OFF WITH 50 SX CMT. PRESSURED THE BACKSIDE TO 200# WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4744	4746		
4697	4700		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
NOV - 8 2017
KCC DODGE CITY



5A

INVOICED
NOV 13 2017