

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-21315-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 13-8S-20W
990 feet from N Section Line, 2310 feet from E Section Line
Lease Name: THYFAULT Well #: 1
County: ROOKS Total Vertical Depth: 3510 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3509		200 SX
SURF	8.625	247		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/27/2017 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TIM JULIAN Company: ABERCROMBIE ENERGY, LLC DB Phone: (620) 793-8185

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/27/2017 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated 2 holes each at 1800', 1495' and 810'. Ran tubing to 3194' and pumped 110 sx cement w/300 # hulls. Pulled tubing to 1806' and pumped 120 sx cement w/200 # hulls to circulate cement to surface. Pulled all tubing and topped off 4 1/2" casing with 25 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 10 sx cement. Shut in pressure 250 psi.

GPS: 39.36236N -099.50092

Perfs:

Top	Bot	Thru	Comments
3379	3383		
3340	3344		
3282	3284		
3209	3212		

Remarks: QUALITY OILWELL CEMENTING TICKET # 331

Plugged through: TBG

INVOICED
DEC 13 2017

District: 04

Received _____
KANSAS CORPORATION COMMISSION

Signed _____

Pat Bedore
(TECHNICIAN)

cm

NOV 20 2017
CONSERVATION DIVISION
WICHITA, KS

NOV 06 2017