

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-21187-00-01  
Spot: S2NENE Sec/Twnshp/Rge: 22-22S-34W  
4322 feet from S Section Line, 650 feet from E Section Line  
Lease Name: NELLANS Well #: 1  
County: FINNEY Total Vertical Depth: 4850 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2500		WITH 2 SX CMT
CIBP		2757		
CIBP	5.5	4700		
DVT	5.5	3339		WITH 325 SX CMT
PROD	5.5	4849	0	WITH 175 SX CMT
SURF	8.625	1944		WITH 750 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/17/2017 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOSE Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: CIBP @ 2500' WITH 2 SX CMT. PERFORATE 4 HOLES AT 1960'. SPOT 50 SX CMT WITH HULLS IN LAST 25 SX CMT. PERFORATE 4 HOLES AT 1100'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/17/2017 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2500' WITH 2 SX CMT. TEST CASING TO 500#. HOLDING. PERFORATE 4 HOLES AT 1960'. INJECTION RATE 2 3/4 BPM AT 1100#. CIRCULATED. PUMP 35 SX CMT, 25# HULLS, THEN 15 SX CMT VIA CASING THROUGH PERFS AT 1960' LEAVING 35 SX CMT OUTSIDE THE CASING & 15 SX CMT INSIDE THE CASING. PERFORATE 4 HOLES AT 1100'. CIRCULATE CMT TO SURFACE WITH 225 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4700			
2597	2603		
2555	2562		

INVOICED  
OCT 18 2017

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED  
OCT 30 2017  
KCC DODGE CITY

Signed

*Ken Jehlik*  
5A

(TECHNICIAN)