

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-21842-00-00
Spot: NWSENWNW Sec/Twnshp/Rge: 26-32S-32W
4563 feet from S Section Line, 4555 feet from E Section Line
Lease Name: ROHR Well #: 1-26
County: SEWARD Total Vertical Depth: 5930 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2560		WITH 2 SX CMT
CIBP		4430		WITH 2 SX CMT
DVT		2964		
PROD	5.5	4848	0	WITH 100 SX CMT
SURF	8.625	1678		WITH 600 SX CMT

Well Type: PI UIC Docket No: D27983.0 Date/Time to Plug: 10/24/2017 8:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: OCTAVIO D MORALES Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: SET CIBP @ 4450' IWHT 2 SX CMT. SET CIBP @ 2560' WITH 2 SX CMT. LOAD & TEST CASING TO 500 PSI. PERFORATE AT 1710' WITH 50 SX CMT & HULLS IN LAST 25 SX CMT. PERFORATE AT 550' WITH CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2017 11:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4430' WITH 2 SX CMT (AS DEEP AS THEY COULD GET). SET CIBP @ 2560' WITH 2 SX CMT. LOADED & TESTED CASING TO 500 PSI. HOLDING. 1ST PLUG PERFORATE AT 1710' WITH 50 SX CMT & 50# HULLS IN LAST 25 SX CMT. 2ND PLUG PERFORATE AT 550' WITH 135 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
4504	4788		
2616	2696		

INVOICED
DEC 13 2017

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY SWIFT.

Plugged through: CSG

District: 01

RECEIVED
OCT 30 2017
KCC DODGE CITY

Signed

Kenny Sullivan
SIA

(TECHNICIAN)