

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-069-20282-00-00  
Spot: NENENW Sec/Twnshp/Rge: 3-29S-30W  
4964 feet from S Section Line, 3002 feet from E Section Line  
Lease Name: REED Well #: 2  
County: GRAY Total Vertical Depth: 4700 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1720		WITH 2 SX CMT
CIBP		4145		WITH 2 SX CMT
PC		2778		WITH 295 SX CMT
PROD 5.5		4699	0	WITH 125 SX CMT
SURF 8.625		807		WITH 425 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/17/2017 3:30 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOSE Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/20/2017 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 4145' WITH 2 SX CMT. ATTEMPT TO TEST CASING. WOULD NOT TEST. PUMPING INTO CASING LEAK AT 2 1/2 BPM AT 200#. 10/18/17: SET CIBP @ 1720' WITH 2 SX CMT. TEST CASING TO 750#. HOLDING. RUN CBL FROM 1700' TO 60'. TOC FOUND AT 816'. PERFORATE 4 HOLES AT 808'. INJECTION RATE 3 BPM AT 100 PSI. RUN TBG TO 1700' & SPOT 35 SX CMT. TOOH WITH TBG. CIRCULATE CMT TO SURFACE THROUGH PERFS AT 808' WITH 240 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT. CMT FALLING BACK. 10/20/17: TOP OFF 5 1/2" WITH 10 SX CMT. TOP OFF ANNULUS WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4195	4430		

INVOICED  
OCT 18 2017

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Ken Jehlik  
JA (TECHNICIAN)

RECEIVED  
OCT 31 2017  
KCC DODGE CITY