

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-15332-00-00  
Spot: W2SENE Sec/Twnshp/Rge: 13-17S-11W  
3300 feet from S Section Line, 990 feet from E Section Line  
Lease Name: MYERS A Well #: 6  
County: BARTON Total Vertical Depth: 3304 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3301		100 SX
SURF	10.75	317		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/25/2017 11:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. DBA Phone: (620) 272-1023

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 500 # hulls and 13 sx gel.  
Junk in hole at 2000'. Will plug from there.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/25/2017 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450', 670' and 325'. Ran tubing to 1993' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1400' and pumped 13 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 700' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 350'. Circulated cement to surface with 75 sx cement. Pulled tubing and topped off with 5 sx cement. Tied to backside and pressured up. Would not take any cement.

GPS: 38.57449 -098.48314

Perfs:

Top	Bot	Thru	Comments
3301	3304		

Remarks: BASIC CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION  
NOV 20 2017  
CONSERVATION DIVISION  
WICHITA, KS

OCT 27 2017

INVOICED  
DEC 13 2017