

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-23494-00-00  
Spot: SESESENW Sec/Twnshp/Rge: 32-9S-20W  
2650 feet from S Section Line, 2380 feet from W Section Line  
Lease Name: FOUR CORNERS Well #: 1-32  
County: ROOKS Total Vertical Depth: 3975 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3974		150 SX
SURF	8.625	221		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/30/2017 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: OCTAVIO D MORALES Company: AMERICAN WARRIOR, INC. DBA Phone: (620) 275-2963

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 18 sx gel (1800 #s) and 500 # hulls.  
Port Collar at 1764' w/150 sx cement.  
Production perforations: 3862' - 3873'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/30/2017 3:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 40 sx cement w/200 # hulls. Well pressured to 1400 psi. Quit pumping. Circulated out to pit. Ran tubing to 3795' and pumped 18 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1888' and pumped 200 sx cement to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing with 20 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pressured immediately to 100 psi.

GPS: 39.22714N -099.57857W

Perfs:

Top	Bot	Thru	Comments
3862	3873		

Remarks: SWIFT SERVICES INC. TICKET # 30858

Plugged through: TBG

INVOICED

NOV 18 2017

District: 04

Received  
KANSAS CORPORATION COMMISSION  
NOV 20 2017  
CONSERVATION DIVISION  
WICHITA, KS

Signed

Pat Bedore  
(TECHNICIAN)

CM

NOV 06 2017