

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-03287-00-00
Spot: NENE Sec/Twnshp/Rge: 34-33S-12W
4628 feet from S Section Line, 672 feet from E Section Line
Lease Name: WRIGHT MERLE E Well #: 1
County: BARBER Total Vertical Depth: 4824 feet

Operator License No.: 6484
Op Name: ANDERSON ENERGY, INC.
Address: 300 W DOUGLAS AVE, STE 410
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4385		WITH 2 SX CMT
PROD	4.5	4824	0	WITH 125 SX CMT
SURF	10.75	309		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/26/2017 12:30 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: PRESTON DREILING Company: ANDERSON ENERGY Phone: (785) 639-2099

Proposed Plugging Method: SET CIBP @ 4650' & 2 SX CMT. PERFORATE AT 600'. CRICULATE CMT TO SURFACE WITH CMT INSIDE & OUTSIDE OF 4 1/2" CASING.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL
Date/Time Plugging Completed: 10/27/2017 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

UNABLE TO GET CIBP BELOW 4385' INSIDE 4 1/2" CASING. SET CIBP AT 4385' & PUT 2 SX CMT ON TOP OF CIB THROUGH DUMP BAILER. PERFORATE 4 1/2" CASING AT 600'. PUMPED DOWN CASING WITH 350 SX CMT. DID NOT GET CMT TO SURFACE. SDON. 10/27/17: RUN TEMPERATURE SURVEY & FOUND TOC @ 400'. PERFORATE 4 1/2" CASING AT 320'. PUMPED DOWN 4 1/2" CASING WITH 150 SX CMT FILLING 4 1/2" CASING & 4 1/2" X 10 3/4" ANNULUS TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4702	4736		
4700	4715		

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed

Stephen J Pfeifer
(TECHNICIAN)
SA

RECEIVED
NOV - 3 2017
KCC DODGE CITY