

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-039-19001-00-03
Spot: SWSESW Sec/Twnshp/Rge: 11-1S-27W
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: WARNER UNIT Well #: 405WSW
County: DECATUR Total Vertical Depth: 3400 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3399		600 SX
SURF	8.625	320		250 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 10/26/2017 9:30 AM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed Plugging Method: 8 5/8 surface casing set @ 320' W/ 250 sx.
5 1/2 production casing set @ 3399' W/ 200 sx. Top of cement: 1867'.
TD 3400'. PBT 1850' W/ CIBP.
DV tool set @ 1867' W/ 400 sx.
Perforations: 1275, 1353, 1587 & 1595'.
Sand fill-up to 1528' W/ 2 sx cement on top.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/26/2017 11:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 1075'. Tagged solid substance. Pulled tubing to 1060' and pumped 110 sx cement mixed with 200 # hulls. Pulled tubing to surface. Connected to 5 1/2 production casing and pumped 20 sx cement. Connected to 8 5/8 surface casing and pumped 5 sx cement. Braden ruptured @ 200 # pressure.

GPS: 39.97409N -100.32165W

Perfs:

Top	Bot	Thru	Comments
3170	3355		
1353	1353		
1275	1275		

INVOICED

OCT 13 2017

Remarks: BACH OIL PRODUCTION SERVICE UNIT. GLOBAL OILFIELD SERVICES CEMENT TICKET #3094.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

NOV 20 2017

CONSERVATION DIVISION
WICHITA, KS

OCT 26 2017