

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-21778-00-00
Spot: E2NWSESW Sec/Twnshp/Rge: 18-33S-31W
1003 feet from S Section Line, 2975 feet from E Section Line
Lease Name: MUSTANG Well #: 1
County: SEWARD Total Vertical Depth: 2660 feet

Operator License No.: 31093
Op Name: BECKER OIL CORPORATION
Address: PO BOX 1150
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2500		WITH 2 SX CMT
PROD	4.5	2659	0	WITH 600 SX CMT
SURF	8.625	542		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/24/2017 9:30 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: DOUG BROWN Company: GLOBAL CEMENTING Phone: (620) 287-4724

Proposed
Plugging
Method:

Set CIBP @ 2500 with 2 sks cement & fill casing with Cement and hook on to Casing head and fill with Cement

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2017 11:30 AM KCC Agent: HEITH WALSH

Actual Plugging Report:

SET CIBP @ 2500' WITH 2 SX CMT. FILL 4 1/2" CASING FROM 2410' TO SURFACE WITH 175 SX CMT. PUMPED 10 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. PRESSURED UP TO 500#.

Perfs:

Top	Bot	Thru	Comments
2553	2637		

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING.

Plugged through: CSG

District: 01

Signed

Heith Walsh

(TECHNICIAN)

5A

RECEIVED
NOV - 9 2017
KCC DODGE CITY

MD