

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-20069-00-00
Spot: SWNESENW Sec/Twnshp/Rge: 14-9S-21W
3453 feet from S Section Line, 3123 feet from E Section Line
Lease Name: HINKHOUSE LEASE Well #: 7
County: GRAHAM Total Vertical Depth: 3689 feet

Operator License No.: 34318

String Size Depth (ft) Pulled (ft) Comments

Op Name: BEREXCO LLC

PROD 5.5 3688 300 SX

Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

SURF 8.625 219 140 SX

SURF 8.625 231

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/01/2017 1:00 PM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Rcvd. from: JEREMY HANKINS

Company: BEREXCO LLC DBA

Phone: (316) 772-8649

Proposed Plugging Method: Ordered 600 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations: 3395' - 3399', 3477' - 3479', 3492' - 3496' and 3584' - 3588'.
DV Tool at 1691' with baroid mud pack
Shot off submersible pump at 2922'. Pump fell to bottom of well. Cable and cable ties wadded up at 525' when pulling tubing. Tubing became stuck. Tied onto tubing with pump truck and still had circulation up outside of tubing.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/01/2017 5:00 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Bottom of tubing at 2922'. Tied onto tubing and pumped 350 sx cement w/400 # hulls. Good circulation of cement to surface. Tied onto backside and squeezed with 10 sx cement. Shut in pressure 100 psi.

GPS: 39.27316 -099.63477

Perfs:

Top	Bot	Thru	Comments
3584	3588		
3492	3496		
3477	3479		
3395	3399		

INVOICED


NOV 13 2017

Remarks: QUALITY CEMENT TICKET # 453

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

NOV 06 2017

NOV 20 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3