

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-147-00975-00-00  
Spot: SENE Sec/Twnshp/Rge: 35-2S-19W  
3300 feet from S Section Line, 660 feet from E Section Line  
Lease Name: DAYTON WATERFLOOD UNI Well #: 8  
County: PHILLIPS Total Vertical Depth: 3545 feet

Operator License No.: 34318

String Size Depth (ft) Pulled (ft) Comments

Op Name: BEREXCO LLC

PROD 5.5 3410 125 SX

Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

SURF 8.625 258 100 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/07/2017 11:00 AM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Rcvd. from: CURT GABLE

Company: BEREXCO LLC

Phone: (785) 623-0546

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.  
Production perforations: 3161' - 3333'.

Plugging Proposal Received By: PAT BEDORE

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 11/07/2017 1:30 PM

KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Perforated 5 1/2" casing at 1532' and 1080'. Ran tubing to 3306' and pumped 125 sx cement w/300 # hulls. Pulled tubing to 2050' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1050' and pumped 200 sx cement w/200 # hulls to circulate 5 1/2" casing and 8 5/8" x 5 1/2" annulus to surface. Pulled all tubing. Topped off 5 1/2" casing with 15 sx cement.

GPS: 39.83736N -099.42405W

INVOICED  
DEC 13 2017

Remarks: GLOBAL CEMENTING TICKET # 3190

Plugged through: TBG

District: 04

Signed  
Received  
KANSAS CORPORATION COMMISSION

Pat Bedore  
(TECHNICIAN)

CM

NOV 20 2017

CONSERVATION DIVISION  
WICHITA, KS

NOV 8 8 2017