

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-23978-00-00
Spot: SENWSW Sec/Twnshp/Rge: 18-34S-3E
1348 feet from S Section Line, 4255 feet from E Section Line
Lease Name: BRANDT Well #: 2
County: COWLEY Total Vertical Depth: 3425 feet

Operator License No.: 35191
Op Name: BUFFALO OIL & GAS, LLC
Address: 119 N. MICHIGAN ST. PO BOX 6
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3424		115 SX
SURF	8.625	307		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/03/2017 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: DON SHORT Company: _____ Phone: (620) 218-1809

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/03/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 3300', GRESSEL OILFIELD ESTABLISHED CIRCULATION, MIXED & PUMPED 25 SXS CLASS A COMMON 2% CC W/40# HULLS & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2450'. TESTED CASING, HELD OK. RIH ON WIRELINE, PERFERATED SQUEEZE HOLES 360'-361' (4 HOLES). SWEDGED INTO 4 1/2" CASING, GRESSEL OILFIELD MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. CEMENT TICKET #44991.

Perfs:

Top	Bot	Thru	Comments
3352	3366	CSG	

**PROCESSED
11.13.17**

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

1/24