

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-30037-00-00  
Spot: W2NWNW Sec/Twnshp/Rge: 24-25S-8E  
660 feet from N Section Line, 330 feet from W Section Line  
Lease Name: WELSH C Well #: 1  
County: GREENWOOD Total Vertical Depth: 2512 feet

Operator License No.: 32701  
Op Name: C & G DRILLING, INC.  
Address: 701 E. RIVER ST.  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2512		100 SX
SURF	8.625	209		135 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/13/2017 10:00 AM  
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.  
Proposal Revd. from: TIM GULICK Company: Phone: (620) 583-4306

Proposed per state requirements  
Plugging  
Method:

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/13/2017 3:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

spotted 10 sxs cement @ 2500' w/dump baler, cut off casing @ 945', pulled casing out, ran tubing to 945' pumped 20 sxs cement, pulled tubing to 250', pumped 80 sxs cement to surface, gel spacers between cement plugs.

Perfs:

RECEIVED  
KCC DIST #3  
NOV 20 2017  
CHANUTE, KS

MH

RECEIVED  
DEC 13 2017

Remarks:

Plugged through: TBG

District: 03

Signed Mitchell Heffern  
(TECHNICIAN)



**ELITE**  
CEMENTING & ACID SERVICE, LLC

**Cement or Acid Field Report**  
Ticket No. **3653**  
Foreman Steve Mead  
Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
11-13-17	1037	Welsh C-1	24	25	8	Greenwood	KS
Customer C & G Drilling Mailing Address 201 E River City Eureka State KS Zip Code 67845			Safety Meeting	Unit #	Driver	Unit #	Driver
				102	Brck		
				110	Tosan		

Job Type <u>PTA</u>	Hole Depth _____	Slurry Vol. _____	Tubing <u>2 3/8</u>
Casing Depth _____	Hole Size _____	Slurry Wt. _____	Drill Pipe _____
Casing Size & Wt. <u>4 1/2</u>	Cement Left in Casing _____	Water Gal/SK _____	Other _____
Displacement _____	Displacement PSI _____	Bump Plug to _____	BPM _____

Remarks: SAFETY Meeting. Rig up to 4 1/2 casing. Break circulation w/ Fresh Water. Mix 200# Gel Flush. Spot 20 sacks Cement AT 945'. Pull out Casing. Run in 250' 2 3/8 Tubing. Break circulation w/ Fresh Water Mix 80 sacks Cement 250' to surface Top well off. Job complete Rig down.

Thank You

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C1062	1	Pump Charge Mileage	\$35.00	\$35.00
C203	100 SKS	69/Kapazmix Cement	12.75	1275.00
C206	340*	Gel 480	.20	68.00
C206	200#	Gel/Flush	.20	40.00
C108A	4.3 Ton	Ton Mileage Bulk Truck	m/c \$	175.00
				Subtotal
				Sales Tax
				<b>Total</b>

**I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.**