

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-02237-00-00
Spot: NESWSESW Sec/Twnshp/Rge: 18-14S-13W
331 feet from S Section Line, 3558 feet from E Section Line
Lease Name: REIN B Well #: 3
County: RUSSELL Total Vertical Depth: 2353 feet

Operator License No.: 6867
Op Name: STEINLE, LA VERN DBA STEINLE OIL
Address: PO BOX 95
BUNKER HILL, KS 67626

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2347		200 SX
SURF	10	430		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/25/2017 10:00 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: LAVERN STEINLE Company: STEINLE, LA VERN DBA STEINLE Phone: (785) 483-1349

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 9 sx gel and 500 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/25/2017 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 300', 850' and 1250'. Cleaned out to 2210' and hit iron. Possible CIB plug. Ran tubing to 2180' and pumped 9 sx gel followed by 50 sx cement w/50 # hulls. Pulled tubing to 1300' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 625' and pumped 100 sx cement w/50 # hulls. Circulated cement to pit. POOH. Hooked to casing and pumped 25 sx cement. Circulated cement to pit out of braden head. Shut in pressure 350 psi.

GPS: 38.82837 -098.81225

Perfs:

Top	Bot	Thru	Comments
2327	2346		

Remarks: GLOBAL CEMENTING TICKET # 3093

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

NOV 20 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

OCT 26 2017

INVOICED
DEC 15 2017