

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-171-20061-00-00  
Spot: SE Sec/Twnshp/Rge: 16-18S-31W  
1320 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: REIFSCHNEIDER Well #: 1  
County: SCOTT Total Vertical Depth: 2815 feet

Operator License No.: 6044  
Op Name: STELBAR OIL CORPORATION, INC.  
Address: 1625 N WATERFRONT PKWY SUITE 2  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1628		
CIBP		2254		WITH 2 SX CMT
PROD	5.5	2815	0	WITH 150 SX CMT
SURF	8.625	363		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/30/2017 9:30 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Revd. from: TY LUNN Company: STELBAR OIL Phone: (316) 440-7611

Proposed Plugging Method: CIBP @ 2250' WITH 2 SX CMT. CIBP @ 1620'. TEST CASING TO 500#. PERFORATE AT 1600'. ESTABLISH INJECTION RATE WITH WATER. SPOT 80 SX CMT 1/2 IN & 1/2 OUT WITH HULLS. PERFORATE AT 385'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/30/2017 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2254' WITH 2 SX CMT. CIBP @ 1628'. TEST CASING TO 650 PSI. HOLDING. PERFORATE 4 HOLES AT 1600'. PUMP 40 SX CMT, 100# HULLS THEN 40 SX CMT. DISPLACE WITH WATER TO 1200' LEAVING 40 SX CMT OUTSIDE THE CASING & 40 SX CMT INSIDE THE CASING. PERFORATE 4 HOLES AT 390'. CIRCULATE CMT TO SURFACE WITH 100 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2744	2752		

INVOICED  
DEC 18 7 17 17

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed

  
(TECHNICIAN)

RECEIVED  
NOV - 3 2017  
KCC DODGE CITY