

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-00186-00-00  
Spot: NW Sec/Twnshp/Rge: 24-21S-33W  
1320 feet from N Section Line, 1320 feet from W Section Line  
Lease Name: ZIRKLE Well #: 1-24  
County: FINNEY Total Vertical Depth: 2695 feet

Operator License No.: 6044  
Op Name: STELBAR OIL CORPORATION, INC.  
Address: 1625 N WATERFRONT PKWY SUITE 2  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2150		WITH 2 SX CMT
PROD	4.5	2695	0	WITH 100 SX CMT
SURF	7	354		WITH 125 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2017 9:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: TY LUNN Company: STELBAR OIL Phone: (316) 264-8378

Proposed Plugging Method: CIBP @ 2150' WITH 2 SX CMT. TEST CASING TO 500#. PERFORATE AT 1150'. INJECTION RATE WITH WATER. 50 SX CMT 1/2 IN & 1/2 OUT WITH 50# HULLS. PERFORATE AT 385'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/01/2017 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2150' WITH 2 SX CMT. TEST CASING TO 500#. HOLDING. PERFORATE 4 HOLES AT 1150'. INJECTION RATE 3 BPM AT 900#. PUMP 25 SX CMT, 50# HULLS THEN 25 SX CMT. DISPLACE WITH WATER AT 1100 PSI LEAVING 25 SX CMT OUTSIDE THE CASING & 25 SX CMT INSIDE THE CASING. PERFORATE 4 HOLES AT 385'. CIRCULATE CMT TO SURFACE WITH 65 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
2664	2686		
2634	2638		


INVOICED  
DEC 18 2017

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_



(TECHNICIAN)

RECEIVED  
NOV - 3 2017  
KCC DODGE CITY