

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-00157-00-00  
Spot: SWSWNESW Sec/Twnshp/Rge: 18-21S-32W  
1337 feet from S Section Line, 3701 feet from E Section Line  
Lease Name: VAN ALLEN Well #: 1-18  
County: FINNEY Total Vertical Depth: 2685 feet

Operator License No.: 6044  
Op Name: STELBAR OIL CORPORATION, INC.  
Address: 1625 N WATERFRONT PKWY SUITE 2  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2150		WITH 2 SX CMT
PROD	4.5	2685	0	WITH 100 SX CMT
SURF	7	351		WITH 100 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2017 1:00 PM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: TY LUNN Company: STELBAR OIL CORPORATION Phone: (316) 264-8378

Proposed Plugging Method: CIBP AT 2150' WITH 2 SX CMT. LOAD HOLE WITH WATER & TEST CASING TO 500#. PERFORATE AT 1200'. INJECTION RATE WITH WATER. 80 SX CMT 1/2IN & 1/2 OUT WITH 50# HULLS. PERFORATE AT 385'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/01/2017 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2150' WITH 2 SX CMT. TEST CASING TO 500#. HOLDING. PERFORATE 4 HOLES AT 1200'. INJECTION RATE 3 BPM AT 500#. PUMP 40 SX CMT, 50# HULLS THEN 40 SX CMT. DISPLACE WITH WATER AT 700# LEAVING 40 SX CMT INSIDE THE CASING & 40 SX CMT OUTSIDE THE CASING. PERFORATE 4 HOLES AT 385'. CIRCULATE CMT TO SURFACE WITH 70 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2656	2672		
2623	2627		

INVOICED  
DEC 18 2017

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed

Ken Jehlik  
(TECHNICIAN)

RECEIVED  
NOV - 3 2017  
KCC DODGE CITY

*MP*