

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-20910-00-00
Spot: SENWNWSE Sec/Twnshp/Rge: 33-18S-31W
2226 feet from S Section Line, 2231 feet from E Section Line
Lease Name: SUPPES Well #: 10B-33-1831
County: SCOTT Total Vertical Depth: 4796 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY SUITE 2
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4300		WITH 2 SX CMT
DVT		3017		WITH 425 SX CMT
PROD	5.5	4796	0	WITH 260 SX CMT
SURF	8.625	392		WITH 240 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2017 8:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: TY LUNN Company: STELABR OIL CORPORATION Phone: (316) 440-7611

Proposed Plugging Method: CIBP @ 4300' WITH 2 SX CMT. PUMP CMT FROM 3050' TO 0'. CHECK ANNULUS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 10/31/2017 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4300' WITH 2 SX CMT. RUN TBG TO 3046' & CIRCULATE CMT TO SURFACE WITH 250 SX CMT. TOP OFF CASING WITH 50 SX CMT. PUMP 10 SX CMT DOWN THE ANNULUS. PRESSURE TO 250 PSI. HOLDING.

Perfs:

Top	Bot	Thru	Comments
4594	4598		
4590	4593		
4388	4392		
4375	4378		

INVOICED
DEC 18 2017

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
SA
(TECHNICIAN)

RECEIVED
NOV - 3 2017
KCC DODGE CITY