

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-22478-00-00  
Spot: SESWSW Sec/Twnshp/Rge: 10-35S-15E  
174 feet from S Section Line, 4126 feet from E Section Line  
Lease Name: RAINS Well #: 1  
County: MONTGOMERY Total Vertical Depth: 1445 feet

Operator License No.: 35473  
Op Name: STREAMLINE ENERGY, LLC  
Address: 906 N. MAIN  
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1407		180 SX
SURF	7.5	77		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/19/2017 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: JUSTIN MORRIS Company: \_\_\_\_\_ Phone: (785) 766-1278

Proposed Pump cement through pipe from bottom to surface. Remove pipe and pressure cement into casing.  
Plugging Method:

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE  
Date/Time Plugging Completed: 09/19/2017 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Shot tubing at 1200' and 1000'. Could not get all of the tubing out of well. Ran 1" inside tubing to 1200' gelled hole and spotted 5 sack plug. Pulled 1". Shot tubing off at 700' (packer must have been set between 1000' and 700'). Pulled 700' of tubing. Ran 1" to 700' and spotted 5 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 40 sacks of cement were used to plug this well.

RECEIVED  
KCC DIST # 3  
NOV 07 2017  
CHANUTE, KS

DS

Remarks:


Plugged through: TBG

INVOICED

DEC 18 2017

District: 03

Signed



(TECHNICIAN)