

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-22723-01-00
Spot: SWNENENE Sec/Twnshp/Rge: 31-21S-7W
4863 feet from S Section Line, 383 feet from E Section Line
Lease Name: RANDOLPH TRUST 2107 Well #: 31-1H
County: RICE Total Vertical Depth: 3499 feet

Operator License No.: 35053
Op Name: TAPSTONE ENERGY, LLC
Address: PO BOX 1608
OKLAHOMA CITY, OK 73101

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	18	62		22 SX CEMENT
I1	7	26		310 sx cement
L1	4.5	6898		265 sx cement
PROD	4.5	6898		265 SX
SURF	9.625	533		375 SX
T1	2.875	2907		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2017 9:00 AM
Plug Co. License No.: 35086 Plug Co. Name: SJL WELL SERVICE, LLC
Proposal Rcvd. from: RANDY SUMMERS Company: SJL WELL SERVICE, LLC Phone: (620) 896-7200

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL WitnessType: PARTIAL
Date/Time Plugging Completed: 11/03/2017 10:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL TUBING. SET CIBP AT 3195' AND CAP WITH 7 SX'S CEMENT. RUN TUBING TO APPROX. 3100' AND PUMP GEL TO SURFACE. RUN CEMENT BOND LOG TO 1500' SHOWING CEMENT TO SURFACE ON BACKSIDE OF 7". RUN TUBING TO 1050' AND PUMP 50 SX'S CEMENT WITH 3% CC. PULL TUBING OUT WAITED TILL NEXT MORNING-TAGGED CEMENT THEN AT 748'. RUN TUBING TO 600' AND PUMPED 115 SX'S CEMENT GETTING CIRCULATION TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
6554	6780	CSG	
6252	6480		
5950	6174		
5637	5876		
5346	5574		
5044	5270		
4653	4968		
4222	4530		
3837	4070		

INVOICED
DEC 18 2017

Remarks: YELLOW JACKET OILFIELD SERVICES WIRELINE. BASIC SERVICES TICKET #16129. TA N.O.V. WELL. TMD = 7416

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

18