

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-01014-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 25-27S-4E
1061 feet from S Section Line, 4992 feet from E Section Line
Lease Name: KING (TWIN) Well #: 1
County: BUTLER Total Vertical Depth: 2030 feet

Operator License No.: 33215
Op Name: TAYLOR, ROBERT W. DBA TAYLOR OI
Address: PO BOX 894
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2018		
PROD	4.5	2030		0 SX
SURF	8.625	140		
SURF	8.625	200		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/06/2017 8:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Rcvd. from: ROBERT TAYLOR Company: _____ Phone: (316) 321-0910

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/09/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/TUBING & TAGGED PACKER @ 1195', PICKED UP 2' AND QES ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS CLASS A COMMON 2% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 1105'. PRESSURED CASING @ 100#, HELD OK. PERFORATED SQUEEZE HOLES @ 260-261' (4 HOLES). SWEDGED INTO 4 1/2" CASING. QES ESTABLISHED CIRCULATION, MIXED & PUMPED 105 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. 11-9-2017, TOPPED WELL BACK TO SURFACE W/ 20 SXS CLASS A COMMON. CEMENT TICKET #54692.

INVOICED
DEC 18 2017

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)