

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21324-00-00
Spot: NWNWSWSW Sec/Twnshp/Rge: 13-20S-16W
992 feet from S Section Line, 4987 feet from E Section Line
Lease Name: O SCHULTZ Well #: 1
County: PAWNEE Total Vertical Depth: 3890 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3662		WITH 2 SX CMT
PROD	5.5	3886	0	WITH 150 SX CMT
SURF	8.625	1105		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/08/2017 9:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO Phone: (785) 625-6374

Proposed Plugging Method: CIBP @ 3755' WITH 2 SX CMT ON TOP. PRESSURE TEST CASING. PERFORATE AT 1150' & 450'. PICK UP TBG & TIH TO 1150'. PUMP 50 SX CMT WITH 100# HULLS IN LAST 25 SX CMT. POOH TO 450' & PUMP CMT TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/08/2017 3:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 3662' WITH 2 SX CMT ON TOP. PRESSURE TEST CASING. WELL WAS TAKING 1 BBL/MINUTE AT 200 PSI. PERFORATE AT 1150' & 450' 2 SHOTS PER FOOT. PICK UP TBG & TIH TO 1150' & PUMP 50 SX CMT WITH 100# HULLS IN LAST 25 SX CMT. POOH WITH TBG TO 450' & PUMP CMT TO SURFACE. 85 SX CMT WAS CIRCULATED TO SURFACE INSIDE 5 1/2" CASING. 105 SX CMT WAS PUMPED OUTSIDE 5 1/2" CASING. DID NOT CIRCULATE TO SURFACE. 11/9/17: 60 SX CMT USED TO FILL ANNULUS BETWEEN 5 1/2" & 8 5/8". 10 SX CMT WAS USED TO FILL 5 1/2" CASING.

Perfs:

Top	Bot	Thru	Comments
3804	3835		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY CEMENTING.

INVOICED
DEC 18 2017

Plugged through: TBG

District: 01

Signed

Ken Scofield

(TECHNICIAN)

RECEIVED
NOV - 9 2017
KCC DODGE CITY

MD

JA