

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-22353-00-00
Spot: NWSENWNW Sec/Twnshp/Rge: 28-19S-28W
816 feet from N Section Line, 852 feet from W Section Line
Lease Name: SPEER 'A' Well #: 1-28
County: LANE Total Vertical Depth: 4656 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	4.5	2093		CEMENTED WITH 190 SX CMT. 20 SX CMT CIRCULATED TO PIT.
PROD	4.5	4650	0	WITH 180 SX CMT
SURF	8.625	223		WITH 165 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/30/2017 1:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Revd. from: MONTE BOYDSTON Company: TRANS PACIFIC OIL Phone: (316) 262-3596

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 50 SX CMT & 200# HULLS. PULL TBG TO 2200' & PUMP CMT UNTIL IT CIRCULATES. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE,

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/01/2017 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4630' & PUMPED 50 SX CMT & 200# HULLS. PULL TBG TO 2150' & PUMPED 170 SX CMT. CMT CIRCULATED. PULLED TBG & PUMPED 20 SX CMT. STAYED FULL. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4650	4656		

INVOICED
DEC 18 2017

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
NOV 18 2017
REG DODGE CITY