

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-21896-00-00
Spot: NESWSE Sec/Twnshp/Rge: 10-19S-28W
997 feet from S Section Line, 1658 feet from E Section Line
Lease Name: BOSLEY TRUST A-C Well #: A1-10
County: LANE Total Vertical Depth: 4700 feet

Operator License No.: <u>9408</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>TRANS PACIFIC OIL CORPORATION</u>	PC	4.5	2167		WITH 250 SX CMT
Address: <u>100 S MAIN STE 200</u>	PROD	4.5	4694	0	WITH 200 SX CMT
<u>WICHITA, KS 67202</u>	SURF	8.625	293		WITH 180 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/30/2017 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Revd. from: MONTE BOYDSTON Company: TRANS PACIFIC OIL Phone: (316) 262-3596

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 50 SX CMT & 200# HULLS. PULL TBG TO 2200' & MIX CMT UNTIL IT CIRCULATES. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE,

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/30/2017 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4300' & PUMPED 50 SX CMT & 200# HULLS. PULL TBG TO 2200' & PUMPED 150 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 35 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4349	4353		

INVOICED
DEC 18 2017

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01 Signed: Michael Maier (TECHNICIAN)

RECEIVED
OCT 31 2017
KCC DODGE CITY

517